

ELECTRICITY

Technical details

Completed

Already installed:

- a 0,80MW transformer (Collini)
- a 1.25 MW transformer (Policontact)
- 6 pillars for street lighting
- Approved Power: 800/870 kW - direct connection (Technical Approval 70002331/21.08.2009);
-
- The existing Sibiu North - ZIOS line has been upgraded with a 20 kV LEA circuit, with 3x150 sqmm twisted cable and 110 pillars, which allows the addition a second circuit;
- Currently there is an approved power of 2.5 MW, according to ATR No. 70201446544/23.09.2014. A 2.0 MW power is still available;

- On the existing 20 kV LEA circuit, an additional 5 MW power is possible up to 2 months after application.

To be completed

Upon investors' request, a second circuit, providing an increase of power, can be completed within 4-6 months.

The project will be delivered by Energotehnica SRL and Energo Smart Invest SRL.

De executat

La cererea investitorilor poate fi realizat al doilea circuit LEA 20kV, cu un spor de putere de 8 MW, în termen de 4-6 luni;

Lucrarea va fi executată de SC ENERGOTEHNICA SRL și ENERGO SMART INVEST SRL